



CONSTRUCTION OF PROPOSED FINANCIAL SERVICES COMMISSION BUILDING
Little Bay, Montserrat

Addendum No: FSC-01

Issue Date: November 30th, 2020

The following modification has been made to the Tender Document to correct an omission in the Bill of Quantities. This modification will affect the calculation of bids and must be included in all Tenders being submitted.

Item 2.1 A in the Measured Works has been modified to add the **quantity amount** and **unit of measurement** which were both un-intentionally omitted from the originally published Tender Document. This item of measured work should read as follows:

Part B 2.0 Measured Works

<i>Item</i>	<i>Description</i>	<i>Qty</i>	<i>Unit</i>	<i>Rate</i>	<i>Amount</i>
2.1	<u>SUBSTRUCTURE</u>				
	<u>Ground Work</u>				
	<u>Excavating and filling</u>				
A	Excavating to reduce levels commencing at existing ground level, maximum depth less than 6ft	561	CY		

Note that the modified Page 1 of the Measured Works is included herewith and the updated full tender package is now available for down load at:

<https://www.fscmontserrat.org/notices/>

Note that the Tender Deadline remains unchanged at 12 Noon 11th, December, 2020.

Signed:

Commissioner, Financial Services Commission

2.0 MEASURED WORKS

<i>Item</i>	<i>Description</i>	<i>Qty</i>	<i>Unit</i>	<i>Rate</i>	<i>Amount</i>
2.1 SUBSTRUCTURE					
<u>Ground Work</u>					
<u>Excavating and filling</u>					
A	Excavating to reduce levels commencing at existing ground level, maximum depth less than 6ft	561	CY		
B	Excavate pits commencing at reduced ground level, maximum depth less than 3'0"	45	CY		
C	Excavate pits commencing at existing ground level, maximum depth less than 3'0"	27	CY		
D	Excavate trenches commencing at reduce ground level, maximum depth less than 3'0"	73	CY		
E	Excavating rock in trenches commencing at ground level maximum depth less than 3'0"	12	CY		
F	Excavate trench commencing at existing ground level, maximum depth 3'0"	13	CY		
G	Working space allowance to excavations				
H	Reduce level excavations	132	SY		
I	Ditto, pits	56	CY		
J	Ditto, trenches	134	SY		
K	Earthwork support, maximum depth less than 3'0", distance between opposing surfaces less than 6'0"	190	SY		
L	Ditto, maximum depth less than 6'0", distance between opposing surfaces greater than 12'0"	132	SY		
<u>Disposal</u>					
M	Surface water drainage		Item		
N	Excavated material off site	670	CY		
O	Filling to excavation with selected material arising from the excavation	48	CY		
P	Filling to make up levels with selected granular fill compacted in layers not exceeding 8" before compaction	524	CY		
Q	Sand blinding, thickness less than 8"	23	CY		
R	Form sinking in compacted fill 2'0" wide x 1'0" deep	4	LY		
To Collection				\$	



CONSTRUCTION OF PROPOSED FINANCIAL SERVICES COMMISSION BUILDING
Little Bay, Montserrat

Addendum No: FSC-01

Issue Date: November 30th, 2020

The following modification has been made to the Tender Document to correct an omission in the Bill of Quantities. This modification will affect the calculation of bids and must be included in all Tenders being submitted.

Item 2.1 A in the Measured Works has been modified to add the **quantity amount** and **unit of measurement** which were both un-intentionally omitted from the originally published Tender Document. This item of measured work should read as follows:

Part B 2.0 Measured Works

<i>Item</i>	<i>Description</i>	<i>Qty</i>	<i>Unit</i>	<i>Rate</i>	<i>Amount</i>
2.1	<u>SUBSTRUCTURE</u>				
	<u>Ground Work</u>				
	<u>Excavating and filling</u>				
A	Excavating to reduce levels commencing at existing ground level, maximum depth less than 6ft	561	CY		

Note that the modified Page 1 of the Measured Works is included herewith and the updated full tender package is now available for down load at:

<https://www.fscmontserrat.org/notices/>

Note that the Tender Deadline remains unchanged at 12 Noon 11th, December, 2020.

Signed:

Commissioner, Financial Services Commission